

Bid No. 19181
Addendum #1

- 1) The painting project Lakes of Long Grove Lift Station and the NCT Grit Washer & piping shall be awarded to a single contractor
- 2) The Gregg's Landing Reservoir shall be awarded separately.
- 3) Lake County Public works has identified approximately 40 cracks within the reservoir. This includes failed or partially failed expansion joints.
- 4) The cracks of concern typically run vertically from the floor to the ceiling.
- 5) A crack shall be classified as an opening or fracture in the concrete where the first injection point begins and extends outward. This can include multiple branches within the crack and is not limited by distance.
- 6) The intent of the crack repair is to seal the wall between the pump room and the reservoir and extending along the side walls to the rear or back wall of the reservoir.
- 7) The most server cracks are to be sealed to address the immediate inflow and infiltration (INI).
- 8) Small or fine cracks shall be completed on a case by case evaluation between the owner and the contractor.

Pictures have been included

Gregg's Landing Reservoir Cracks

