

Bid Item. #	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
	GENERAL REQUIREMENTS				
1	Mobilization / Project Administration / Demobilization	LS	1		
2	Pre-construction Video	LS	1		
3	Temporary Facilities	LS	1		
	SOIL EROSION CONTROL / PRE-CONSTRUCTION PREPARATION				
4	Silt Fence	LF	165		
5	Inlet Baskets	EA	10		
6	Sediment Containment Filter Bag	LS	1		
7	Cofferdam	LS	1		
8	Erosion Control Maintenance & Removal	LS	1		
9	Tree Protection & Pruning	LS	1		
10	Tree Removal	UNIT DIA	450		
11	Shrub/Brush Removal	LS	1		
	CONSTRUCTION PREPARATION				
12	Traffic Control & Protection	LS	1		
13	Existing Fence Removal and Replacement	LS	1		
14	Temporary Construction Fencing	LS	1		
	FORCE MAIN CONSTRUCTION				
15	Sanitary Force Main, 12" PVC C900, Open Cut	LF	15		
16	Sanitary Sewer, PVC 12"	LF	20		
17	Sanitary Sewer, PVC 18"	LF	330		
18	Sanitary Sewer, PVC 24"	LF	1,150		
19	Sanitary Sewer, Water Main Quality Pipe, 12"	LF	50		
20	Storm Sewer, PVC, 12"	LF	20		
21	Triple Barrel Siphon Installation	LS	1		
22	ComEd Soil Disposal (Allowance)	LS	1		\$ 14,000
23A	Connect to Existing Force Main (Including Required Fittings)	EA	1		
23B	Connect to Existing Existing Sanitary Sewer	EA	2		
23C	Connect to Existing Sanitary Manhole	EA	1		
24	Sanitary Manholes, Type A, 4'-Diameter, Type 1 Frame & Lid	EA	2		
25	Sanitary Manholes, Type A, 5'-Diameter, Type 1 Frame & Lid	EA	4		
26	Sanitary Manholes, 5'x5', Special	EA	2		
27	Sanitary Manholes, 6'x6', Special	EA	2		
28	Storm Inlet, Type A, w/ Salvaged Frame and Lid	EA	1		
29	Precast Drop Connection	EA	1		
30	Sanitary Manholes to be Removed	EA	5		
31	Sanitary Manholes to be Abandoned	EA	3		
32	Remove and Replace Unsuitable Material	CY	50		
33	Sanitary Sewers to be Removed within COMED Right-of-Way	LS	1		
34	Sewers to be Abandoned / Removed	LS	1		
35	Sanitary Force Main to be Removed	LF	630		
36	Sewer Abandonment with Controlled Low-Strength Material	LS	1		
37	Remove and Reset Concrete Box Culverts	LS	1		
38	Water Main Removal and Replacement	LS	1		
39	Temporary Bypass Operations	LS	1		
	RESTORATION				
40	Concrete Driveway Removal and Replacement	LS	1		
41	Pavement Restoration Class D Patch (2" Surface / 4" Binder)	LS	1		
42	Pavement Restoration Resurface (2" Surface)	LS	1		
43	Aggregate Shoulder (CA-6), Removal and Replacement	LS	1		
44	Concrete Sidewalk Removal and Replacement, 5"	SF	225		
45	Concrete Curb and Gutter Removal and Replacement, B6.12	LF	570		
46	Preparation of Disturbed Lawn Area and Placement of Topsoil	LS	1		
47	Seed / Fertilize / Erosion Blanket Over Disturbed Lawn Areas	LS	1		
48	Sewer Televising	LS	1		
TOTAL BID =					

	SUPPLEMENTAL UNIT PRICING	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
A	Pavement Restoration Class D Patch (2" Surface / 4" Binder)	SY			
B	Aggregate Shoulder (CA-6)	SY			
C	Preparation of Disturbed Lawn Area and Placement of Topsoil	SY			
D	Seed / Fertilize / Erosion Blanket Over Disturbed Lawn Areas	SY			