8/6/2021 **REVISED** 9/10/2021

| Bid Item. # | DESCRIPTION | UNIT | QUANTITY | UNIT PRICE | TOTAL PRICE |
|-------------|---|----------|----------|---------------------|-------------|
| | GENERAL REQUIREMENTS | | | | |
| 1 | Mobilization / Project Administration / Demobilization - Wellington FM | LS | 1 | | |
| 2 | Mobilization / Project Administration / Demobilization - Three Lakes FM | LS | 1 | | |
| 3 | Mobilization / Project Administration / Demobilization - Cedar Crest FM | LS | 1 | | |
| 4 | Pre-construction Video | LS | 1 | | |
| 5 | Temporary Facilities | LS | 1 | | |
| | SOIL EROSION CONTROL / PRE-CONSTRUCTION PREPARATION | | | | |
| 6 | Silt Fence | LF | 670 | | |
| 7 | Inlet Baskets | EA | 6 | | |
| 8 | Tree Protection Fence | LF | 500 | | |
| 9 | Ditch Checks | EA | 9 | | |
| 10 | Sediment Containment Filter Bag | LS | 1 | | |
| 11 | Erosion Control Maintenance & Removal | LS | 1 | | |
| 12 | Tree Protection & Pruning | LS | 1 | | |
| 13 | Tree / Shrub Removal | LS | 1 | | |
| | CONSTRUCTION PREPARATION | | | | |
| 12 | Traffic Control & Protection - Wellington FM | LS | 1 | | |
| 13 | Traffic Control & Protection - Three Lakes FM | LS | 1 | | |
| 14 | Traffic Control & Protection - Cedar Crest FM | LS | 1 | | |
| 15 | Temporary Construction Fencing | LS | 1 | | |
| | FORCE MAIN CONSTRUCTION | | | | |
| 16 | Sanitary Force Main, 4" | LF | 1,490 | | |
| 17 | Sanitary Force Main, 6" | LF | 1,510 | | |
| 18 | Long Sweep 45 Degree Bends, 4" | EA | 11 | | |
| 19 | Long Sweep 45 Degree Bends, 6" | EA | 7 | | |
| 20 | Connection to Existing Sanitary Manhole (Including Required Fittings) | EA | 1 | | |
| 21 | Connection to Existing Lift Station (Including Required Fittings) | EA | 3 | | |
| 22 | Tracer Wire Station | EA | 9 | | |
| 23 | Tracer Wire Signal Testing / Continuity Confirmation | LS | 1 | | |
| 24 | Cut and Plug Existing Force main | EA | 7 | | |
| 25 | Excavated Spoil Offsite Disposal | LS | 1 | | |
| 26 | Directional Drill Spoil Offsite Disposal | LS | 1 | | |
| 27 | Force Main Pressure Testing | LS | 1 | | |
| 28 | Pig Launch and Retrieval | LS | 1 | | |
| 29 | Sanitary Manholes to be Removed | EA | 2 | | |
| 30 | Sanitary Manholes, Type A, 4'-Diameter, Type 1 Frame & Lid | EA | 2 | | |
| 31 | Drilling / Pulling Pit Adjacent to Paved Surface (Excavation / Shoring / Trench Backfill) | EA | 7 | | |
| 32 | Drilling / Pulling Pit in Lawn Area (Excavation / Shoring / Backfill) | EA | 3 | | |
| 33 | Pig Launch Station, 4" - Complete | EA | 2 | | |
| 34 | Pig Launch Station, 6" - Complete | EA | 1 | | |
| 35 | Three Lakes Meter (Supply Only) | LS | 1 | | |
| 36 | Three Lakes Meter (Installation) | | | | |
| | RESTORATION | | | | |
| 37 | Pavement Restoration Class D Patch (2" Surface / 4" Binder) | LS | 1 | | |
| 38 | Pavement Restoration Class D Patch (2" Surface / 2.5" Binder) | LS | 1 | | |
| 39 | Aggregate Shoulder (CA-6) | LS | 1 | | |
| 40 | Concrete Sidewalk Removal and Replacement, 5" | LS | 1 | | |
| 41 | Preparation of Disturbed Lawn Area and Placement of Topsoil | LS | 1 | | |
| 42 | Seed / Fertilize / Erosion Blanket Over Disturbed Lawn Areas | LS | 1 | | |
| | | | | | |
| | | | | | |
| | OCTOR TOTO TOTO TOTO TOTO TOTO TOTO TOTO | LO | ' | | |
| 43 44 | Tree Installation, Match Existing Size & Species Sewer Televising | EA LS | тот | 2 1 TAL BID A | |

| CONTRACTOR SELECTED PIPING MATERIAL | FORCE MAIN MATERIAL TO BE INSTALLED |
|-------------------------------------|-------------------------------------|
| WELLINGTON FORCE MAIN - 4" | |
| THREE LAKES FORCE MAIN - 4" | |
| CEDAR CREST FORCE MAIN - 6" | |

| | SUPPLEMENTAL UNIT PRICING | UNIT | QUANTITY | UNIT PRICE | TOTAL PRICE |
|---|---|------|----------|------------|-------------|
| Α | Class D Pavement Patch (2" Surface / 4" Binder) | SY | | | |
| В | Aggregate Shoulder Patch | SY | | | |
| С | Seed and Erosion Control Blanket Installation | SY | | | |
| | | | | | |