



Department of Public Works

Austin McFarlane
Director

650 W. Winchester Road
Libertyville, Illinois 60048
Phone 847 377 7500
Fax 847 984 5665

PublicWorks@lakecountyil.gov

Project: Oak Terrace Well House
Interconnect and System Improvements
Bid# 24227
PW# 2015.003
1/18/2024

Addendum 1

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated December 2023, with amendments and additions noted below.

This Addendum consists of one (1) page, including:

- Revisions to the Project Manual
- Questions and Clarifications

PROJECT MANUAL REVISIONS

1. Section 40 95 13, Process Instrumentation and Control Equipment
 - a. Replace Paragraph 1.8.B. with the following:

“The Integrator shall be able to program the required updates to the existing Master Site Equipment.

1. Acceptable Integrators:
 - a. Concentric Integration, 815-788-3600, Crystal Lake, IL
 - b. Wunderlich-Malec, 630-827-0200, Addison, IL
 - c. Allan Integrated Control Systems, Inc., 262-642-7800, East Troy, WI”

QUESTIONS AND CLARIFICATIONS

Question 1: PR-200 calls for a 4” check valve for the well piping. Are there specific requirements for the well check valve?

Answer 1: Yes, the well check valve shall be the Surgebuster model check valve manufactured by Val-Matic.