

BID FORM
FOR
Saunders Road Water Main
Village of Libertyville, Illinois

ITEM NO	IDOT CODE	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	VALUE
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	100.0	UNIT	\$	\$
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	100.0	UNIT	\$	\$
3	20101100	TREE TRUNK PROTECTION	15.0	EA	\$	\$
4	20101200*	TREE ROOT PRUNING (SPECIAL)	200.0	FT	\$	\$
5	*	TREE AND LANDSCAPE MATERIAL PROTECTION (SPECIAL)	200.0	FT	\$	\$
6	20101400	NITROGEN FERTILIZER NUTRIENT	60.0	LBS	\$	\$
7	20101600	POTASSIUM FERTILIZER NUTRIENT	60.0	LBS	\$	\$
8	20101700	SUPPLEMENTAL WATERING	40.0	UNIT	\$	\$
10	20800150*	TRENCH BACKFILL (SPECIAL)	380.0	CY	\$	\$
11	21101615	TOPSOIL FURNISH AND PLACE, 4"	2,650.0	SY	\$	\$
12	25000210	SEEDING, CLASS 2A	0.6	AC	\$	\$
13	25100630	EROSION CONTROL BLANKET	2,650.0	SY	\$	\$
14	28000400	PERIMETER EROSION BARRIER	530.0	FT	\$	\$
15	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	400.0	SF	\$	\$
16	44000200	DRIVEWAY PAVEMENT REMOVAL	100.0	SY	\$	\$
17	44000600	SIDEWALK REMOVAL	400.0	SF	\$	\$
18	44201696	CLASS D PATCHES, TYPE IV, 4 INCH	330.0	SY	\$	\$
19	Z0004510*	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	100.0	SY	\$	\$
20	48101498	AGGREGATE SHOULDERS, TYPE B 4"	35.0	SY	\$	\$
21	56100600*	WATER MAIN 6", DUCTILE IRON CL 52, OPEN CUT (SPECIAL)	230.0	FT	\$	\$
22	56100700*	WATER MAIN 8", PVC C900 DR 18, OPEN CUT (SPECIAL)	230.0	FT	\$	\$
23	56100700*	WATER MAIN 8", PVC C900 DR 18, DIRECTIONALLY DRILLED (SPECIAL)	5,650.0	FT	\$	\$
24	56100800*	WATER MAIN 10", DUCTILE IRON CL 52 OPEN CUT (SPECIAL)	40.0	FT	\$	\$
25	56400500*	FIRE HYDRANTS TO BE REMOVED	10.0	EA	\$	\$
26	*	SALVAGE EXISTING FIRE HYDRANT	1.0	EA	\$	\$
27	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	13.0	EA	\$	\$
28	*	TRACER WIRE	6,150.0	FT	\$	\$
29	*	WATER SERVICE CONNECTION, LONG SIDE-1.5"	25.0	EA	\$	\$
30	*	WATER SERVICE CONNECTION, SHORT SIDE - 1.5"	12.0	EA	\$	\$
31	*	SAMPLE STATION	1.0	EA	\$	\$
32	60248700*	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID (SPECIAL)	14.0	EA	\$	\$
33	67100100	MOBILIZATION	1.0	LSUM	\$	\$
34	*	DRILLING/PULLING PIT	16.0	EA	\$	\$

35	*	CONNECTION TO EXISTING WATER MAIN, NON PRESSURE (SPECIAL)	8.0	EA	\$	\$
36	*	CUT AND CAP WATER MAIN	6.0	EA	\$	\$
37	*	REMOVE VALVE VAULT (SPECIAL)	8.0	EA	\$	\$
38	*	REMOVE GUARD RAIL	1.0	LSUM	\$	\$
39	X0100029"	EXPLORATORY EXCAVATION (SPECIAL)	12.0	EA	\$	\$
40	X2140100*	GRADING AND SHAPING DITCHES (SPECIAL)	250.0	FT	\$	\$
41	X0100003	CLEARING AND GRUBBING	1.0	LSUM	\$	\$
42	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	1.0	LSUM	\$	\$
43	*	REMOVE AND RESET STREET SIGN	3.0	EA	\$	\$
44	*	CASING PIPE, 16"	40.0	FT	\$	\$
45	*	REMOVE EXISTING WATER MAIN (SPECIAL)	120.0	FT	\$	\$
46	*	DECORATIVE WOODCHIPS (SPECIAL)	15.0	SY	\$	\$
47	*	COIR LOG	15.0	EA	\$	\$
					BASE BID TOTAL:	\$
ALTERNATE #1						
48	56100700*	WATER MAIN 8", DUCTILE IRON CL 52, DIRECTIONALLY DRILLED (SPECIAL)	5,610.0	FT	\$	\$
					ALT BID TOTAL:	\$